

3/11/2020

Client Responsibility & Preparation for Maya-625A

To download client **must** have a **20000 LB forklift** with long forks **or a crane**

Shipping Manager: Kerem (310) 767-1770

The time for downloading must not exceed 1 hours, every extra hour will cost \$95.-.

For the installation you will need a forklift (8000 LB including a driver)

Concrete level floor and One man to help the tech.

220V 3 phase power ready wires for the main machine panel. (+/-5%) regulated. (60Amp.)

The Volts & Hertz of the installation location must be specific for the transformer (A30KVA) (220 3PH 60Amp. 50/60 Hz)

Power Cables (Transformer to control panel) an electrician must be on site at **start** of installation, and be done the first day.

Prepare also 48 anchors (5.5" x 3/4" red head) you can buy at local Home Depot.

Heavy duty hammer drill.

Water hose to the machine. We recommend changing the water hose on the machine with a high-pressure hose.

Client responsible to cover the table with 4x4 treated wood + concrete (recommended 2") [max. load 2,500LB] after installation.

All this must be ready before we can send a technician to install.

Installation takes maximum 2 days any extra day technician on a nun prepared site will be charged \$900/day.

Note: Please take pictures of the shipment when arrive (damage must be reported asp) if not all damages in shipment will be your responsibility. Delivery of the saw is on a half flat bed and is subject to the availability of trucking company.

Storage: In case client cannot receive the item, after 2 weeks of item in our storage client will be responsible for the storage fee \$100/month.

Self-install will wave warranty. After installation all warranty repairs or tech question should be directed to The Machine Tech

Technician Info	Client info
 <p>James Darnell The Machine Tech (877) 262-1500 Work info@themachinetech.com Po Box 10986 Parkville MD 21234 http://www.themachinetech.com/</p>	